



RESIDENTIAL METERS

ITEM	DESCRIPTION	5/8", 5/8" X 3/4"	3/4" METER	1" METER
A	FULL FLOW VALVE WITH HANDLE			
B	METER & COUPLING DIMENSION	12"	13-3/8"	15-1/4"
C	PRESSURE REDUCING VALVE			
D	RESIDENTIAL DUAL CHECK VALVE			
E	SPLIT RING HANGER			
F	ALL-THREAD			
G	MOUNTING BRACKET	3/4"	3/4"	1"
H	METER COUPLING			
I	METER LAYING LENGTH	7-1/2"	9"	10-3/4"

NOTES:

1. NOTIFY AUTHORITY WHEN WATER SERVICE IS READY FOR INSPECTION & TEST. DO NOT BACKFILL TRENCH UNTIL INSPECTION IS COMPLETED.
2. LOCATION OF METER & REGISTER TO BE APPROVED BY AUTHORITY.
3. AUTHORITY WILL INSTALL METER AND REMOTE READING REGISTER.
4. ALL SERVICE LINES SHALL BE MINIMUM 3/4" CONTINUOUS TYPE "K" COPPER OR PE TUBING - NO COUPLINGS.
5. PROVIDE ELECTRICAL BONDING AS REQUIRED BY CODE.
6. ALL WORK WILL BE SECURELY FASTENED TO THE WALL TO SUPPORT THE METER.
7. PLUMBER RESPONSIBLE TO INSTALL METER COUPLINGS

HORSHAM WATER & SEWER AUTHORITY

DETAIL W9

**INSIDE INSTALLATION
RESIDENTIAL METERS
5/8" x 3/4", 3/4" & 1"**

DATE: MARCH 23, 2015

SCALE:
NOT TO SCALE